Tender No: BMRCL/Phase-3/JPN-MRS/Demolition/DLN-P1/2026/157

BANGALORE METRO RAIL PROJECT, PHASE-3

Name of the Work: "Partial and Full Demolition/Dismantling of Buildings/Structures identified in Bangalore Metro Rail Project Phase-3."

Contract Package-P1: "Partial and Full Demolition/Dismantling of Buildings/Structures identified from JP Nagar 4th Phase Station to Mysore Road Station (from Ch: (-) 0.330 Km to Ch: 10.550 Km) in Corridor-1 of Bangalore Metro Rail Project Phase-3."

FINANCIAL DOCUMENT
(Pricing Document)

VOLUME - 4

SEPTEMBER-2026

SECTION – J: FINANCIAL DOCUMENT- PRICING DOCUMENT

Name of Work: "Partial and Full Demolition/Dismantling of Buildings/Structures identified in Bangalore Metro Rail Project Phase-3."

Contract Package-P1: "Partial and Full Demolition/Dismantling of Buildings/Structures identified from JP Nagar 4th Phase Station to Mysore Road Station (from Ch: (-) 0.330 Km to Ch: 10.550 Km) in Corridor-1 of Bangalore Metro Rail Project Phase-3."

Tender Notification No: BMRCL/Phase-3/JPN-MRS/Demolition/DLN-P1/2026/157

PRICING DOCUMENT - LETTER OF PRICE BID
(To be submitted in the letter head of the Tenderer)

Ref: Dated…….

(Tenderer to provide date and reference no.)

To
The Managing Director,
Bangalore Metro Rail Corporation Ltd.
Fourth floor, BMTC Complex
KH Road, Shanthinagar
Bangalore-560027, Karnataka,
India.

Dear Sir,

Priced document for …… (Name of Work) and …….. (Tender No.).

1. We, hereby submit our priced document for the above-mentioned work.

2. We understand that in the event of any information furnished by us being found later on to be incorrect or any material information having been suppressed, the following action can be taken in addition to the Provisions of Clause 4.33 of General Conditions of Contract (GCC).

   (i) Any tender submitted by us in future for other works on the basis of qualification may not be considered.

   (ii) If any tender from us is accepted and a contract awarded to us on the basis of our qualification, the tender acceptance may be withdrawn and the contract awarded to us may be cancelled without any financial claim /Arbitration request from our side.

   (iii) Our name will / may be removed from the panel of qualified agencies.

Yours faithfully,

(Signature) ……

Name of signatory: ……

Capacity of signatory: ……

Name and address of Tenderer:……..

Pricing Document-Preamble

1. The Pricing Document-Bill of Quantities (BOQ) & Abstract to Bill of Quantities (BOQ) shall be read in conjunction with the entire Tender and Contract Document including Instructions to Tenderers, General Conditions of Contract (including 'Contract Data'), Special Conditions of Contract, Notice Inviting Tender, Technical Specifications, Employer's Requirements, Scope of work, Schedule, Attachments, Appendix, Annexure, Corrigendum and Addendums.
2. The quantities given in the Price document - "Bill of Quantities" are estimated (provisional). The basis of payment will be the actual quantities of work ordered and carried out, as measured by the Contractor and verified by the Engineer and valued at the rates in the accepted priced "Price Bid – Summary of Bill of Quantities".
3. Tenderer shall quote in the Price Bid (.xls format) sheet only in accordance with the ITT clause 10. Tenderer is advised to quote their percentage rate in two decimals for Schedule-A. Tenderer has to select option "At Par / Excess / Less" and enter percentage rate in figures on estimated cost to Schedule-A, for Schedule-B tenderer is required to select percentage option as 'At Par' only and for Schedule-C tenderer shall offer Credit to BMRCL on Salvage of Materials, in 'Lump sum' amount.
4. The Lump sum amount indicated for Schedule C will be recovered from the running account bills proportionately. In case of any variation in Quantities (increase/decrease), the value of credit to BMRCL will be increased/decreased according to the value of work done from the 'on account' bills on pro-rata basis.
5. The Contractor should note that the credit to BMRCL on salvage materials should be in reference to the quoted price and not on the estimate cost put to tender.
6. The 'Tender Price' or 'Quoted Price' includes all applicable taxes, duties, cess, royalties, and statutory levies as per the laws in force as on last day of the month previous to the month of invitation of this tender, except Goods and Services Tax (GST).
7. The method of measurement of completed work for payment shall be in accordance with the requirements as stated in the Technical Specifications and as given in the Price document- Bill of Quantities or elsewhere in the tender documents.
8. The quoted price is for completed and finished items of work and complete in all respects complying with the provisions of the Contract. It will be deemed to have included all constructional plant, machinery tools, fuel, oil, consumables, electric power, water, transportation, disposal of debris at BBMP/GBA identified C&D waste management facility (dismantled/demolished material), all leads & lifts, all temporary works & false works, fencing, watering, lighting, maintenance, night working and inspection facilities.
9. The quoted price will be deemed to have included all the safety measures at work sites/ casting yard, safety measures for workmen & road users, safety of the public and protection of adjoining land & building while working.
10. The quoted price will be deemed to have included establishment & overhead charges, contractor's profit, supervision, other charges together with all general risks, liabilities and obligations set out or implied in the contract and including remedy of any defects during the Defect Liability Period.
11. The quoted price will be deemed to have included accommodations for staff & workmen, all insurance costs for labour & works, the payment of all wages, salaries, fees if any, charges payable to various departments for obtaining necessary approvals if any.

12. The work is to be executed as per Bill of Quantity description, Technical Specifications, specifications of MORTH, KPWD, CPWD, drawings, best engineering practices and/or as directed by the Engineer.
13. Removal of hoardings, interior lighting and interior furniture etc., ACP cladding and structural glazing etc., which are existing within the line of cut are incidental to work. No separate payment will be considered for payment.
14. If it is necessary to maintain any power, water or other utilities during demolition, such lines shall be temporarily relocated, as necessary and protected before commencement of demolition work.
15. All such cost involved for temporary relocation/maintenance must be borne by contractor and no payment will be made for temporary works. The contractor shall make his own arrangements for power requirement for his equipment/machinery. If advised by the Consultant/BMRCL, the contractor has to give temporary supports for the building during demolition wherever necessary without any extra financial implications to BMRCL.
16. If advised by the Consultant/BMRCL, the contractor has to give permanent supports like wall, columns (Steel, RCC, etc.), including plastering, painting, plumbing, water supply and sanitary works, electrical restoration works, etc. to the supported portion of the building before or after total/partial demolition, wherever necessary to maintain LOC, for which payment will be made as per accepted rate in BoQ schedule for items available in Common SR for the year 2023-24 (Schedule of Rates), for the execution of such work.
17. 50% area of Balcony and Canopy if exists will be considered for calculating area for payment as per the guide lines for valuation of properties. The area of chejjas or such similar coverings/shadows will not be considered for payment.
18. The demolition and dismantling shall be carried out up to ground and/or up to basement level as the case may be including underground water storage structures if any. Refilling the low-level areas up to ground level is within the scope of contractor’s work.
19. The items existing excluding trees within the proposed line of cut have to be dismantled and demolished and debris to be transported and disposed.
20. The total floor area means the summation of total built area of all floors in the buildings indicated in Schedule A.
21. In case some buildings are deleted or added in BOQ, the rates per sqm for that deletion/addition will be same as given above. For payment purpose, the %age quoted and accepted in the Summary Cost will be used for the above rate.

PRICING DOCUMENT- ABSTRACT OF BILL OF QUANTITIES (BOQ)

Name of the Work-: **"Partial and Full Demolition/Dismantling of Buildings/Structures identified in Bangalore Metro Rail Project Phase-3."**

Contract Package-P1: "Partial and Full Demolition/Dismantling of Buildings/Structures identified from JP Nagar 4th Phase Station to Mysore Road Station (from Ch: (-) 0.330 Km to Ch: 10.550 Km) in Corridor-1of Bangalore Metro Rail Project Phase-3."

Tender Notification No: BMRCL/Phase-3/JPN-MRS/Demolition/DLN-P1/2026/157, Dated. 09.09.2026

Sl.No	Schedule	Schedule Description	Total Estimated Cost (Rs)
1	SCHEDULE-A	Partial & Full demolition and dismantling work as per details given in Schedule-A of the BOQ	**4,69,41,306.00**
2	SCHEDULE-B	Items under Schedule of Rate published by KPWD	**5,00,000.00**
		Total of Schedules (A+B)	**4,74,41,306.00**
3	SCHEDULE-C	Credit to BMRCL for salvageable items out of dismantled/demolished private properties on which the owner has no interest (as elaborated in Para 15 of Part-3 of 'Employer's Requirement').	----

Pricing document- Bill of Quantities (BOQ)					
	Schedule - A				
Item No.	**Description of Item of work**	**Unit**	**Quantity**	**Rate (in Rs)**	**Total Amount (In Rs)**
1	**Partial** demolition/dismantling by mechanical and manual methods of all types of structures of different heights consisting of ground floor and/or more than one floors, (RCC framed structures, wall bearing structures with RCC roof. All other structures such as AC roof etc), comprising of cement concrete, stone masonry, brick work, steel work, wood work etc. Disposal of unserviceable materials with all leads and lifts and stacking of serviceable materials, the stacked serviceable material shall be disposed of with all leads and lifts in which the property owner has no interest, removal of resulting debris with all lead and lifts, including necessary strengthening methods for the buildings proposed for demolition and also for neighbouring buildings, complete in all respects.	Sqm	31245.00	1087.00	3,39,63,315.00
2	**Full** demolition/dismantling by mechanical and manual methods, of all types of structures of different heights consisting of ground floor and/or more than one floors (RCC framed structures, wall bearing structures with RCC roof. All other structures such as AC roof etc), comprising of cement concrete, stone masonry, brick work, steel work, wood work etc. Disposal of unserviceable materials with all leads and lifts and stacking of serviceable materials, the stacked serviceable material shall be disposed of with all leads and lifts in which the property owner has no interest, removal of resulting debris with all lead and lifts, including necessary strengthening methods for the buildings proposed for demolition and also for neighbouring buildings, complete in all respects.	Sqm	21760.00	548.00	1,19,24,480.00
3	Demolition /dismantling compound walls of all shapes and heights by mechanical and manual methods, comprising of cement concrete, stone masonry work,	Rmt	5183.00	167.00	8,65,561.00

Pricing document- Bill of Quantities (BOQ)					
	Schedule - A				
Item No.	**Description of Item of work**	**Unit**	**Quantity**	**Rate (in Rs)**	**Total Amount (In Rs)**
	brick work, fencing, stone slab wall, chain link fencing etc. disposal of unserviceable materials with all leads and lifts and stacking of serviceable materials, the stacked serviceable material shall be disposed of with all leads and lifts in which the property owner has no interest, removal of resulting debris with all lead and lifts and complete.				
4	Demolition/dismantling of steel structures such as sign boards, hoardings etc., of all heights, length and width by mechanical and manual methods. (Dismantled/released material to be handed over to the concerned authority at the locations specified by owning authority and removal of resulting debris with all lead and lifts).	MT	25	7518.00	1,87,950.00
	Total of Schedule-A				**4,69,41,306.00**
Schedule-B					
	ITEMS UNDER SCHEDULE OF RATE PUBLISHED BY KPWD				
1	Items not covered in the above Schedule A to be executed under Common SR for the year 2023-24 published by Karnataka public Works Department with issue rates and amendments issued upto date of tender submission.	**Lump sum**	**---------**	**---------**	**5,00,000.00**
				Total Schedule A+B	**4,74,41,306.00**